



NOTES:

1. WHERE SIDEWALK, CURB AND GUTTER EXIST, SIDEWALK, CURB AND GUTTER SHALL BE REMOVED AND REPLACED TO THE NEAREST JOINT AND SHALL BE CONSTRUCTED PER APPLICABLE CITY OF CLOVIS STANDARD DRAWINGS.
2. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN AN ENCROACHMENT PERMIT FOR ANY WORK WITHIN THE CITY RIGHT OF WAY, INCLUDING THE REMOVAL AND REPLACEMENT OF THE SIDEWALK, CURB AND GUTTER AND THE CONSTRUCTION OF THE RESIDENTIAL UNDER SIDEWALK DRAIN, FROM THE CITY OF CLOVIS ENGINEERING DIVISION.
3. THE CONTRACTOR SHALL CALL IN A LOCATION REQUEST TO UNDERGROUND SERVICE ALERT (USA) TWO WORKING DAYS PRIOR TO DIGGING. NO INSPECTION WILL BE PROVIDED AND NO CONSTRUCTION PERMIT ISSUED INVOLVING EXCAVATION FOR UNDERGROUND FACILITIES WILL BE VALID UNLESS THE APPLICANT HAS BEEN PROVIDED AN INQUIRY IDENTIFICATION NUMBER BY USA.
4. THE CONTRACTOR SHALL PROVIDE A CERTIFICATE OF INSURANCE NAMING THE CITY OF CLOVIS AS AN ADDITIONAL INSURED IN ACCORDANCE WITH THE ENCROACHMENT PERMIT PROCESS.
5. THE ENGINEER OF RECORD SHALL DETERMINE THE NUMBER OF DRAINS REQUIRED.



CITY OF CLOVIS

DWG NO.

SD-3

RESIDENTIAL SIDEWALK DRAIN

APPROVED BY:

CITY ENGINEER

DATE: *6/21/09*

NO.	REVISED	BY	APPROVALS
	03-13-09	BGJ	CM <i>[Signature]</i> DRU <i>[Signature]</i> PUD <i>[Signature]</i>

SCALE: NTS

DRAWN BY: SS

SHEET 1 OF 1