



CITY OF CLOVIS  
**CONFORMED AND VALIDATED BID RESULT ON 8/1/23**  
**CIP 21-11 Fowler Avenue Street Improvements**

CITY of CLOVIS

**PROJECT ENGINEER:**

Jacob Redelfs

**PROJECT LOCATION:**

Fowler Avenue from Ashlan Avenue to City Limits

**PROJECT SCOPE OF WORK:**

This project includes rehabilitation of Fowler Avenue from Ashlan Avenue to Clovis City Limits. Rehabilitation consists of but is not limited to the grinding, excavating and replacing of six-inches of existing asphalt pavement, modifying existing median noses, replacing curb and gutter, replacing traffic signal loop detectors, adjusting sewer manholes to finished grade, and re-striping and signing the road to match the existing Fowler Avenue.

ITEM	DESCRIPTION	QUANTITY	UNIT	Engineer's Estimate		Emmett Valley Construction, Inc.		Avison Construction, Inc.		UNIT PRICE	EXTENSION
				UNIT PRICE	EXTENSION	UNIT PRICE	EXTENSION	UNIT PRICE	EXTENSION		
<b>Base Bid Items for Fowler Avenue Street Improvements</b>											
1.	Mobilization	1	LS	\$ 30,000.00	\$ 30,000.00	\$ 7,000.00	\$ 7,000.00	\$ 30,000.00	\$ 30,000.00		\$ -
2.	Traffic Control	1	LS	\$ 30,000.00	\$ 30,000.00	\$ 12,000.00	\$ 12,000.00	\$ 21,500.00	\$ 21,500.00		\$ -
3.	Storm Water Pollution Prevention Plan	1	LS	\$ 3,000.00	\$ 3,000.00	\$ 3,000.00	\$ 3,000.00	\$ 500.00	\$ 500.00		\$ -
4.	Dust Control	1	LS	\$ 2,000.00	\$ 2,000.00	\$ 1,000.00	\$ 1,000.00	\$ 100.00	\$ 100.00		\$ -
5.	Grind Asphalt Concrete	4,177	SY	\$ 4.00	\$ 16,708.00	\$ 4.30	\$ 17,961.10	\$ 6.00	\$ 25,062.00		\$ -
6.	Asphalt Concrete, "Type A"	2,107	TON	\$ 100.00	\$ 210,700.00	\$ 113.00	\$ 238,091.00	\$ 132.00	\$ 278,124.00		\$ -
7.	Cold Plane AC Pavement	4,154	SY	\$ 3.00	\$ 12,462.00	\$ 3.10	\$ 12,877.40	\$ 4.50	\$ 18,693.00		\$ -
8.	Adjusting Sanitary Sewer Manhole to Finish Grade	3	EA	\$ 1,200.00	\$ 3,600.00	\$ 1,200.00	\$ 3,600.00	\$ 2,000.00	\$ 6,000.00		\$ -
9.	Adjusting Domestic Water Valve Box to Finish Grade	1	EA	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00		\$ -
10.	Adjusting Sanitary Sewer Valve Box to Finish Grade	1	EA	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,000.00	\$ 1,200.00	\$ 1,200.00		\$ -
11.	Concrete Median Island Curb	17	LF	\$ 100.00	\$ 1,700.00	\$ 115.00	\$ 1,955.00	\$ 200.00	\$ 3,400.00		\$ -
12.	Concrete Curb and Gutter	195	LF	\$ 60.00	\$ 11,700.00	\$ 73.00	\$ 14,235.00	\$ 100.00	\$ 19,500.00		\$ -
13.	Concrete Median Island Cap	23	SF	\$ 55.00	\$ 1,265.00	\$ 116.00	\$ 2,668.00	\$ 100.00	\$ 2,300.00		\$ -
14.	Detectable Warning Device	1	EA	\$ 1,000.00	\$ 1,000.00	\$ 800.00	\$ 800.00	\$ 600.00	\$ 600.00		\$ -
15.	Traffic Striping and Signage	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 8,000.00	\$ 8,000.00	\$ 10,000.00	\$ 10,000.00		\$ -
16.	Traffic Signal Modification	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 17,000.00	\$ 17,000.00	\$ 23,500.00	\$ 23,500.00		\$ -
17.	Traffic Loop Detector	10	EA	\$ 800.00	\$ 8,000.00	\$ 1,100.00	\$ 11,000.00	\$ 800.00	\$ 8,000.00		\$ -
<b>Total Base Amount</b>					<b>\$ 364,135.00</b>		<b>\$ 353,187.50</b>		<b>\$ 449,479.00</b>		<b>\$ -</b>

**LOW BIDDER**

**REMARKS:**

This project is scheduled for award approval from the City Council on August 7, 2023.